

ADDENDUM NO. 1**OWNER:** District of Chetwynd**PROJECT:** 2019 Sanitary Main Replacement**DATE:** Feb 28, 2019**TENDER REF.:** 181-15378-00**TENDER CLOSING DATE:** March 5, 2019**TO ALL TENDERERS:**

- 1) On drawing 001, detail B, replace road structure with “75 Asphalt, 150mm 19mm Minus Base, 400mm 75mm Minus Subbase”
- 2) Replace Form of Tender – Appendix 1 Schedule of Quantities and Prices with the attached form.

These items shall be incorporated into the Contract Documents. This Addendum shall be signed and submitted with the Tender Form.

WSP Canada Inc.

Acknowledged by:

-----
Tenderer's SignatureKevin Wiens, P.Eng,
Contract Administrator-----
Date



FORM OF TENDER – Appendix 1

SCHEDULE OF QUANTITIES and PRICES

ITEM	DESCRIPTION	UNIT	EST. QTY	UNIT PRICE	ESTIMATED AMOUNT
A GENERAL					
A.1	SS 2.1 Mobilization (50%) / Demobilization (50%)	LS	1		
A.2	SS 2.2 General Conditions, Admin, Insurance	LS	1		
A.3	SS 2.3 Survey Layout & Record Markups	LS	1		
SECTION A SUBTOTAL					
B SITE WORK - 51st AVE SW					
B.1	SS 2.17 Erosion and Sediment Control	LS	1		
B.2	SS 2.4 Sawcut, Remove and Dispose Asphalt				
	a) 6m wide	LM	25		
	b) Driveway - Tim Hortons	LS	1		
	c) Driveway - Chevron #1	LS	1		
	d) Driveway - Chevron #2	LS	1		
B.3	SS 2.5 Remove and dispose of manholes, Cap Main. Backfill with compacted native material	ea	1		
B.4	SS 2.6 Break into AC pipe to facilitate tie-ins, remove and dospose safely as required	LS	1		
B.5	Dewatering along trench including premium for 25" smooth rock for pipe bedding (optional)	LM	100		
B.6	Dispose of Unsuitable Backfill and Imported Backfill (Optional)	m3	300		
B.7	SS 2.8 Road or Paved Driveway Restoration				
	31 32 19 a) Geotextile (optional)	m2	650		
	32 11 16.1 b) SubBase Course Gravel (75mm crush) - 400mm depth	m2	650		
	32 11 23 c) Surface Course Gravel (19mm crush) - 150mm depth	m2	650		
	32 12 16 d) Hot Mix Asphalt - 75mm in 2 lifts	m2	400		
	e) Cast in Place Curb	LM	50		
B.8	SS 2.9 Gravel Driveway Restoration	ea	4		
B.9	32 92 19 SS 2.10 Topsoil (150mm) & Hydroseeding	m2	1200		
B.10	33 44 01 SS 2.11 Remove and Replace Catchbasins	ea	1		
SECTION B SUBTOTAL					



C		SEWERMAIN - 51st AVE SW			
C.1	33 30 01 SS 2.12	Sanitary Sewer - 200mm Diameter SDR 35 PVC			
		a) 0-4m depth (Sta 107 to 0+382)	LM	280	
C.2	33 30 01	Sewer Service - Tie existing service to main	ea	10	
C.3	33 30 01 SS 2.12	Replace or extend sewer service to property line - restoration in item B.7 (Optional)			
		a) 100mm dia. (optional)	LM	6	
		b) 150mm dia (optional)	LM	6	
C.4	33 44 01 SS 2.14	Manholes - 1050mm dia - including excavation, bedding, backfill, frame & cover, benching			
		a) Manhole with precast bases	ea	3	
		b) Manhole over existing, including breaking into pipe and tying in (optional)	ea	1	
C.5	33 44 01 SS 2.14	Tie to existing manholes	ea	3	
C.6		Tanks & Pumping to maintain sewer service during construction	LS	1	
C.7	33 01 30.1 SS 2.15	Video inspection & Report	LS	1	
C.8	33 11 01 SS 2.16	Deflection of 150mm dia watermain (optional)	ea	1	
SECTION C SUBTOTAL					
D		SITE WORK - 53rd PLACE NW			
D.1	SS 2.17	Erosion and Sediment Control	LS	1	
D.2	SS 2.4	Sawcut, Remove and Dispose Asphalt			
		a) STA 0+410 to 0+487 - 6m wide	LM	100	
D.3	SS 2.6	Break into AC pipe to facilitate tie-ins, remove and dospose safely as required	LS	1	
D.4		Dewatering along trench	LM	25	
D.5		Dispose of Unsuitable Backfill and Imported Backfill (Optional)	m3	300	
D.6	SS 2.8	Road or Paved Driveway Restoration			
	31 32 19	a) Geotextile (optional)	m2	1200	
	32 11 16.1	b) SubBase Course Gravel (75mm crush) - 400mm depth	m2	1200	
	32 11 23	c) Surface Course Gravel (19mm crush) - 150mm depth	m2	1200	
	32 12 16	d) Hot Mix Asphalt - 75mm in 2 lifts	m2	600	
D.7	32 92 19 SS 2.10	Topsoil (150mm) & Hydroseeding	m2	100	
SECTION D SUBTOTAL					



E		SEWERMAIN - 53rd PLACE NW			
E.1	33 30 01 SS 2.12	Sanitary Sewer - 200mm Diameter SDR 35 PVC			
		a) 0-4m depth	LM	194	
E.2	33 30 01 SS 2.12	Sanitary Sewer - Pipe Bursting - 200mm HDPE pulled back through existing	LM	53	
E.3	33 30 01	Sewer Service - Tie existing service to main	ea	10	
E.4	33 30 01 SS 2.12	Replace sewer service to property line - restoration in item B.7 (Optional)			
		a) 100mm dia.	LM	30	
		b) 150mm dia	LM	30	
E.5	33 44 01 SS 2.14	Tie to existing manholes	ea	8	
E.6	33 01 30.1 SS 2.15	Video inspection & Report	LS	1	
SECTION E SUBTOTAL					
					SUBTOTAL
					GST (5%)
					TOTAL